



FOOTING & FOUNDATION NOTES:

- SEE MAIN FLOOR PLAN FOR HOLDPOIN PLACEMENT
- PLACE REINFORCING STEEL 3" TO 4" FROM THE INSIDE FACE OF THE WALL
- PLACE (2) #4 BARS 3" FROM THE TOP AND BOTTOM OF THE FOUNDATION WALL
- PLACE (2) #4 BARS AROUND ALL OPENINGS IN THE FOUND. WALL
- 3"x8" FOUND. WALL W/ #4 BAR @ 24" O/C VERT. (3) #4 BARS HORIZ.
- 8"x8" FOUND. WALL W/ #4 BAR @ 24" O/C VERT. (6) #4 BARS HORIZ.
- 12"x10" A-BOLTS @ 32" O/C MAX.
- W/ 2"x2"x3/16" EP WASHERS
- (FT) 20X10 CONC. FTG. W/ 2-#4 BARS CONT. IN FTG.
- (FT) 18X10 CONC. FTG. W/ 2-#4 BARS CONT. IN FTG. (INT.)

9' FOUND. HGT. (FOUR @ 8' @)
FTG. FOUND. PLAN
 SCALE 1/4"=1'-0"

8" CONC. LID WHEN 3/4" F.I. ARE USED. F.I.S. USED W/ #4 STAB. OF FOUND. & 7" O/C BENT INTO LID. W/ #4 BAR & 7" O/C EA. W/ 1" N. LID. SEE BUILDER.

NOTE:
 FOR COMBUSTION AIR SUPPLY SEE #4 SHUTTER WATER HTR SEE (E1A)

COMPACT FILL 95%

SEE STEEL POST DETAIL IN CALC. Q1401 TPO-2000B SQD SPOT SI INWD

SEE STEEL POST DETAIL IN CALC. Q1401 TPO-2000B SQD SPOT SI INWD

DESIGNED BY: _____
 DRAWN BY: _____
 JOB # _____
 DATE _____
 SHEET # **3**

REVISIONS

FTG. FOUND. & BSMNT. PLAN

A RESIDENCE FOR:
WILKERSON, RICHARD
 LOCATION:
 UTAH

J FISK DESIGNS
 931 WEST CENTER (BSMNT) OREM, UTAH 84057
 (801) 225-7631 FAX (801) 229-2676