



INSPECTION PORT AT END OF EVERY RUN SEE DETAIL CE3.3

DRAIN FIELD AREA 8000 SQ FT

- NOTES:**
1. INSTALLATION OF INFILTRATOR SYSTEM PER MANUFACTURERS INSTRUCTIONS
 2. INSTALL INFILTRATOR SYSTEM USING SAME END SERIAL DISTRIBUTION (SEE CE3.3 FOR SAME END SERIAL DISTRIBUTION DETAILS)
 3. INSTALL BACKFLOW VALVE AT OUTLET OF EACH SEPTIC TANK
 4. TRENCHES SPACED OC AT 6'
 5. INSTALL FLOAT ALARM AT 80% LEVEL OF SEPTIC SYSTEM
 6. TRENCHES TO BE FILLED WITH 1 1/2" - 2" GRAVEL TO A MIN 6" DEPTH
 7. GEOTEXTILE TO BE PLACED ON ALL TRENCH RUNS TO PREVENT TOPSOIL CONTAMINATION (SEE CE3.3 FOR DETAILS)
 8. 13000 GAL SEPTIC TANKS TO BE CONNECTED IN PARALLEL. EACH TANK TO HAVE A TURN OFF VALVE INSTALLED BEFORE TANK INLET
 9. ALL FITTINGS MUST BE NO MORE THAN 45 DEGREE BEND
 10. 4" SCHEDULE 40 FOR ALL RUNS UNLESS OTHERWISE NOTED
 11. ALL FITTINGS, VALVES, AND PIPES SHOULD BE PLACED BY INSTALLER NEAR LOCATIONS GIVEN IN DRAWING
 12. GRAVITY DRAINFIELD REQUIRES A SANDY GRAVEL SOIL PROFILE
 - 13.

SEPTIC TANKS & DRAIN FIELD DETAIL

SCALE 1"=10'-0"



QUINALT ENGINEERING
 14 WEST QUINALT ST. TAHOLA, WA 98577
 (509) 374-6115 (425) 330-3514
 WWW.QUINALTENGINEERING.COM

PROJECT: CAONE JOURNEY 2013 AND BEYOND
 SCALE 1:120 REVISION: A, 1

DESIGNED BY: BJM
 DATE: 8/29/2012

SHEET CONTENTS: DRAIN FIELD DETAIL

REVISION HISTORY:

SHEET	CUSTOMER: QUINALT INDIAN NATION
	LOCATION: TAHOLAH, WA
CE3.2	
Of CE4	